





1. ALL MATERIAL AND CONSTRUCTION METHODS USED SHALL CONFORM TO PENNSYLVANIA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS PUB. 408, LATEST EDITION WITH ALL UPDATES AND REVISIONS.
2. SUPERPAVE ASPHALT MIX DESIGN, HMA WEARING COURSE, PG64-22,03 TO 3.0 MILLION E.S.A.L.S. 9.5 MM MIX, SRL-M
3. CONCRETE SIDEWALKS DISTURBED WILL BE REPLACED FULL WIDTH, FROM EXISTING JOINTS, IN ACCORDANCE WITH PENNDOT SECTION 876 AND STANDARD DRAWING RC-87M.
4. PROVIDE TRAFFIC CONTROL IN ACCORDANCE WITH PENNDOT SECTION 901.

DESIGN BY: R. A. D.	CHECKED BY:	DATE: 12/19/13
---------------------	-------------	----------------

DRAWN BY: R. A. D.	REVISIONS:	SCALE: N. T. S.
--------------------	------------	-----------------

BOROUGH OF HOMESTEAD – PAVED SURFACE RESTORATION

GLENN ENGINEERING & ASSOCIATES LTD.  
 14920 Route 30 – North Huntingdon, PA

DRAWING NO.:  
 IX :